CODE SCREEN - RNGD 2021 IBC RULE SET (planning level, not a code determination)

RULE	CHECK	REQUIRED	PROVIDED	STATUS
-	Keys placed	117	117	PASS
IBC-R1-007	Stories above grade	<= 5 (Type IIA, sprinklered R-1)	6	FAIL
IBC-R1-005	Building height (ft)	<= 85 (Type IIA)	69.8	PASS
IBC-R1-010	Area per story (SF)	<= 72,000 (Type IIA)	13,575	PASS
IBC-R1-012	High-rise screen (ft to top floor)	<= 75	59.0	PASS
IBC-R1-015	Exits per story	2 for 1-500 occupants	2 stairs; max load 316	PASS
IBC-R1-018	Exit separation (ft)	>= 1/3 diagonal = 75	207	PASS
IBC-R1-023	Exit access travel (ft)	<= 250 (sprinklered)	130	PASS
IBC-R1-025	Corridor width (in)	>= 44	72	PASS
IBC-R1-027	Dead-end corridor (ft)	<= 50 (sprinklered R-1)	5	PASS
IBC-R1-028	Egress door clear width (in)	>= 32	34 (3'-0" leaf)	PASS
IBC-R1-003	Automatic sprinklers	NFPA 13 required	assumed	ASSUMED
ADA-224.2	Accessible guest rooms (mobility)	>= 7 for 117 rooms (5 + 2 with roll-in)	7	PASS
ADA-224.4	Rooms with communication features	>= 12	not designated	REVIEW
ADA-224.5	Dispersion across room types	spread over 3 types	3 types: king, suite,...	PASS
-	Fits buildable envelope	170 x 265 ft	234 x 58 ft	PASS

* IBC-R1-007: Level 1 counts as a story above grade plane. A Type IA podium (IBC 510.2) could allow 5 stories above it.

* IBC-R1-023: Half the stair-to-stair run plus the room depth.

* ADA-224.2: Confirm which 2 of the ADA units get roll-in showers (Table 224.2).

* ADA-224.4: Designate 12 rooms; at most 10% of the mobility rooms may count (224.5).

PROGRAM SUMMARY

Keys	117
Net program area	59,350 SF
Gross, source sheets	74,195 SF (ratio 1.25)
Gross, 33% circ. + 8% walls	85,300 SF
Gross, drawn schematic	76,508 SF
Levels	6 (Level 1 + 5 guest floors)
Height to roof	69.8 ft
Tower / podium length	217 ft / 234 ft x 58 ft
Program source	Project Renegade Living + Lodging Prototype, cover sheet (06/20/25)

ASSUMPTIONS

- Envelope from the app sidebar (default synthetic lot 170 x 265 ft). Street assumed on the south side.
- Double-loaded corridor, 6 ft clear; room depth 26 ft; room width = program area / 26 ft.
- Floor-to-floor: Level 1 16 ft, guest floors 10.75 ft (from the L+L elevations).
- Core at the west end (Stair 1, two elevators, shafts); Stair 2 at the east end of the north side.
- Rows whose count equals the number of guest floors (Ice, IT, Jan, Supplies) are placed once per floor.
- Room mix spread evenly across floors, largest units first. Fixtures and furniture are typical, not from RNGD unit drawings.
- Occupant loads use the RNGD CSV factors (IBC Table 1004.5); lobby as assembly unconcentrated (15 SF net).

OPEN QUESTIONS FOR RNGD

1. Which area of the Level 1 / Level 2 drawing was meant? The reference coordinate note (scale 1.08 to the original image) did not name a room, stair or gridline. Please mark the spot on the L+L plans sheet.
2. Story limit: the program needs Level 1 plus five guest floors (six stories), but RNGD rule IBC-R1-007 allows five stories for sprinklered Type IIA R-1. Is a Type IA podium (IBC 510.2) intended, as in the L+L prototype?
3. Confirm the gross-up rule: kickoff meeting said 33% circulation + 8% wall burden; the L+L source sheets imply 1.25.
4. Real lot, setbacks, street frontage and fire-lane requirements (the envelope used here is synthetic).
5. Is parking part of this phase? It is not modelled.
6. Confirm the per-floor support rooms (Ice, IT, Jan, Supplies) and the Level 1 BOH arrangement.
7. Column grid: 30-34 ft bays assumed from the kickoff meeting. Is there a preferred structural module?
8. Prefab panel / module catalog to replace the indicative panel breakdown on the elevations.